

Fabrication Load for TLT

Report logic — snapshot · Vijay Transmission Pvt. Ltd.

A Reports-page view of fabrication workload by project and weight (tonnes), for TLT orders. Each of five operations is shown in two states: **Operational Load** — work sitting AT that operation now; and **In Hand** — work that has not yet reached it. Projects carry a user-set Priority (P1–P10).

The two states

- **Operational Load** = the work currently AT the operation (ready / in progress there now).
- **In Hand** = the work still upstream — it has not reached the operation yet, so it is coming.

The five operations and their rules

Operation	Operational Load (AT)	In Hand (BEFORE)
Welded Load	Marks currently at W	Marks before W in the sequence (C,RFI,NH,B,HAB,HG) — not W
Bending Load	Marks currently at B	Marks before B (C,RFI,NH) — not B
Drilling Load	Angle + at RFI + qualifies Drilling	Angle + at C + qualifies Drilling
Plate Punch	Plate + at RFI + qualifies Punching	Plate + at C + qualifies Punching
Plate Drill	Plate + at RFI + qualifies Drilling	Plate + at C + qualifies Drilling

Welded & Bending use a POSITIONAL rule (at the activity = Operational; earlier in the sequence = In Hand). Drilling / Plate Punch / Plate Drill use a SPECIFIC-ACTIVITY rule (RFI = Operational, C = In Hand) combined with the section type and its punch/drill qualification.

How punch vs drill is decided (recap)

- **Angle** and **Plate**: thickness ≤ 12 mm → Punching; > 12 mm → Drilling (below the minimum → Punching).
- **Channel, Beam, RSJ**: always Drilling (not used in the Plate/Angle columns here).
- Thickness: angle = last dimension of the section; plate = the plate's mm value.

What each column shows

- Projects that have matching work, each with its **weight in tonnes** (Balance Wt ÷ 1000, 3 decimals).
- A **G. Total** per column (sum of that column's project weights).
- A **Priority** dropdown per project row: P1–P10, set by the user, saved.
- Scope: **TLT orders only**. A project appears in a column only if it has matching weight there.

Illustrative layout (one column)

Welded Load — Operational		
Project	Weight (t)	Priority
929	24.261	P1
848	52.851	P2
926	11.212	P3
G. Total	88.324	

(Figures illustrative. Each of the 5 operations has its own Operational and In-Hand column like this.)

In one line: for five fabrication operations, the report splits each project's weight into “at the operation now” (Operational) and “still upstream” (In Hand), in tonnes, with a user-set priority — TLT only.